

Checking after Servicing and Repairs

When the air conditioning has been filled, the following connection points must be checked with a leak tester:

- Two connections on the accumulator/dehydrator.
- Two connections on the evaporator.
- One connection on the compressor.
- Two connections on the condenser.
- Two filling valves.

If leaks are discovered, drain the air conditioning system. Use one of the recommended servicing units. Afterwards renew the leaking or faulty part. If necessary, rectify the quantity of oil according to the table above.